

## **ADDENDUM #2**

TO  
THE CONTRACT DOCUMENTS FOR THE CONSTRUCTION OF

### **HERNANDO BEACH VOLUNTEER FIRE DEPARTMENT BUILDING ADDITION**

IN  
HERNANDO COUNTY, FLORIDA  
CEO # SOLICITATION NO. 10-0015  
REVISED BID OPENING DATE: **10 FEBRUARY 2010**

#### NOTICE

BIDDERS ARE REQUIRED TO ACKNOWLEDGE RECEIPT OF THIS  
ADDENDUM BY SIGNATURE AT THE BOTTOM OF THIS ADDENDUM IN  
THE SPACES PROVIDED AND RETURNED AT THE TIME OF THE BID DATE.

TO ALL PLAN HOLDERS:

The following changes, additions, and/or deletions are hereby made a part of the  
Contract Documents for the HBVFD ADDITIONS located in Hernando County,  
as fully and completely as if the same were fully set forth therein:

#### **I. CLARIFICATIONS**

1. Soils report is attached.
2. Building will be non-insulated.
3. The walkway between the new building and the existing building shall be covered with sheet metal, not T-111. There will be bare studs in the walkway, no wall coverings.
4. Plans Sheet 1 is the Cover sheet. Plans Sheet 10 is for SWFWMD only and not included in the bid package.
5. Flood vents are required for the new building.
6. The areas to be sodded are the DRA and any area disturbed by the contractor.
7. The palm trees and fire station sign in front of HBVFD are to remain.
8. The contractor shall be responsible for relocating all utilities.
9. Anything in the footprint of the new building is the contractor's responsibility to remove or relocate (utilities).
10. Foundation plans are to be provided by the metal building supplier through the contractor. Slab must be designed to withstand a 60,000lb fire truck loading.
11. Building roof to match existing building for slope, and ridge direction. Ridge vents are to be 40'.
12. The sanitary sewer shall not to be relocated.
13. The overhead power lines get relocated underground by the contractor. The fiber optic line will be relocated to a temporary line by Brighthouse. Once the building site work is done the contractor shall bury this line. When done the power, phone, and cable will all be underground.
14. The new building does not have any water, plumbing, or gas. The only new utility is electric.

15. The area west of the building is for maneuver room for training and moving around fire trucks.
16. The 4 gang outlets are changed to quad receptacles.
17. The electric door openers are push button openers for the bay doors. The contractor is responsible for the electric door openers and the installation of them.
18. The roofing shall be screw down roofing.
19. Overhead doors can be sectional or roll up.

## **II. SPECIFICATIONS**

1. Revised specifications attached. Replace all specifications with the attached.

## **III. PLANS**

Acknowledged

---

J. D. GANTT, CPPO, C.P.M.,  
Purchasing and Contracts, Director

Issued:           22 January 2010