

LINE NO.	PAY ITEM	DESCRIPTION	UNIT	QTY	UNIT PRICE	AMOUNT
1	101-1	MOBILIZATION	EA	1		
2	102-1	MAINTENANCE OF TRAFFIC	L.S.	1		
3	104-13-1	STAKED SILT FENCE, TYPE 3	L.F.	24115		
4	110-1	CLEARING AND GRUBBING, INCLUDES FENCE & CONCRETE REMOVAL	L.S.	1		
5	110-7-1	MAILBOX, P&I, SINGLE	EA	56		
6	120-1	REGULAR EXCAVATION	L.S.	1		
7	120-2	BORROW EXCAVATION	L.S.	1		
8	120-4	SUBSOIL EXCAVATION	CY	1600		
9	120-6	EMBANKMENT	L.S.	1		
10	285-70-1	OPTIONAL BASE GROUP 1, LIMEROCK 4", LBR 100	S.Y.	13525		
11	285-70-13	OPTIONAL BASE GROUP 13, LIMEROCK, 13.5", LBR 100	S.Y.	7485		
12	286-1	TURNOUT CONSTRUCTION CONCRETE	S.Y.	125		
13	286-2	TURNOUT CONSTRUCTION ASPHALT ( DRIVEWAYS and SIDE STREETS)	TN	105		
14	327-70-6	MILLING, EXISTING ASPHALT, 1.5" (AVG) DEPTH	S.Y.	1500		
15	337-7-33	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, 1.5", FC-12.5, RUBBER	TN	3742		
16	334-1-13	ASPHALT CONCRETE STRUCTURE COURSE, TRAFFIC C, 1.5", SP-12.5	TN	1235		
17		OPEN GRADED MIX, ASPHALT STRESS RELIEF, 1.25" (MIN)	TN	3333		
18	400-1-2	CONCRETE CLASS 1, ENDWALLS	C.Y.	3		
19	430-174-101	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 0-24", SD	L.F.	72		
20	430-174-201	PIPE CULVERT, OPTIONAL MATERIAL, OTHER - ELLIP/ARCH, 0-24", SD	L.F.	144		
21	430-174-202	PIPE CULVERT, OPTIONAL MATERIAL, OTHER - ELLIP/ARCH, 25-36", SD	L.F.	24		
22	430-982-129	MITTERED END SECTION, OPTIONAL ROUND, CD 24"	EA	2		
23	430-984-629	MITTERED END SECTION, OPTIONAL ELLIP/ARCH, SD 24"	EA	14		
24	430-984-633	MITTERED END SECTION, OPTIONAL ELLIP/ARCH, SD 30"	EA	2		
25	440-1-20	UNDERDRAIN, TYPE II, 4" DIA.	L.F.	600		
26	520-1-10	CONCRETE CURB and GUTTER, TYPE F	L.F.	600		
27	524-2-49	CONCRETE SLOPE PAVEMENT, 6" REINFORCED	S.Y.	55		
28	530-1	RIP-RAP	C.Y.	6		
29	536-1-1	GUARDRAIL, ROADWAY	L.F.	100		
30	536-2	GUARDRAIL, SHOP BENT PANELS, 24' RADIUS	L.F.	75		
31	536-85-22	GUARDRAIL, END ANCHORAGE ASSEMBLY, FLARED	EA	4		
32	570-1-2	PERFORMANCE TURF, SOD	SY	76875		
33	700-20-40	SINGLE POST SIGN, RELOCATE	AS	42		
34	706-3	RETRO-REFLECTIVE PAVEMENT MARKERS	EA	680		
35	710-11-111	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	N.M.	8.92		
36	710-11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 12"	L.F.	96		
37	710-11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 24"	L.F.	100		
38	710-11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	10		
39	710-11-221	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID 6"	N.M.	5.1		
40	710-11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID 18"	L.F.	1002		
41	710-11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP 6"	G.M.	0.76		
42	711-11-111	THERMOPLASTIC, STANDARD, WHITE, SOLID, 6"	N.M.	4.46		
43	711-11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12"	L.F.	48		
44	711-11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24"	L.F.	50		
45	711-11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	5		
46	711-11-211	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 6"	N.M.	2.55		
47	711-11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18"	L.F.	501		
48	711-11-231	THERMOPLASTIC, STANDARD, YELLOW, SKIP, 6"	G.M.	0.38		
		GRAND TOTAL				

Revisions:  
 1 2/10/2010 SEN ADDENDUM ONE

**HERNANDO COUNTY FLORIDA**  
**Department of Public Works**  
 ENGINEERING DIVISION  
 1525 East Jefferson Street  
 Brooksville, FL 34601-2807  
 Ph. (352) 754-4062 Fax. (352) 754-4423

INVALID UNLESS  
 SIGNED, DATED, & SEALED  
 CHRISTOPHER S. WERT, P.E.  
 FL. REG. P. E. No. 48216

**SPRING LAKE HIGHWAY**  
**SUMMARY OF PAY ITEMS**  
 Scale: N.T.S.  
 Drawn By: SEN  
 Project Engineer: C.WERT, P.E.  
 Drawing Number: SPRINGLAKEHWY  
 Sheet No. 2 of 27  
 CEO No.

ADDENDUM ONE