

ADDENDUM NO. 4

**TO
THE CONTRACT DOCUMENTS
FOR THE HERNANDO COUNTY UTILITIES DEPARTMENT
THE WEEKI WACHEE WASTE WATER TREATMENT PLANT BYPASS PROJECT
IN**

HERNANDO COUNTY, FLORIDA

SOLICITATION NO. 10-0083

REVISED BID DATE: Wednesday, September 15, 2010 at 3:00 p.m.

NOTICE

**BIDDERS ARE REQUIRED TO ACKNOWLEDGE RECEIPT OF
THIS ADDENDUM BY SIGNATURE AT THE BOTTOM OF
THIS ADDENDUM IN THE SPACES PROVIDED AND
RETURNED AT THE TIME OF THE BID DATE.**

To All Bidders:

This Addendum forms a part of the Contract Documents and modifies the Bidding Documents dated August 2010 with amendments and additions noted below. Acknowledge receipt of this Addendum in the space provided in the Bid Form. Failure to do so may disqualify the Bidder.

Changes to the Project Bid Specifications

1. There will be no pigging of the force main or water main required.
2. Geotechnical Services will be the responsibility of the contractor as stated in general note # 31.
3. Builders risk insurance is required as part of this project.
4. See revised bid schedule to be included in the bid specs for this project. Disregard revised bid schedule with Add # 3
5. The County shall award the Bid on the lowest most responsive Base bid or on the lowest Bid including the Bid Alternative. Bid decision will be made in the County's best interest. Bid items 72, 73, 74, 75 will replace 7,9,11,15 if it is in the County's best interest.
6. In Section V – 012000 Measurement and Payment under Bid Item Description # 20 please add the following sentence to the end of paragraph a. Also add paragraph f for payment.
 - a. This item is for additional restoration outside of the limits for the pipe line trench.

- f. Payment shall be made under
Asphalt Driveway/Roadway Restoration for paragraphs b, c, and e.
Concrete Sidewalk Restoration for paragraph d.

ACKNOWLEDGMENT

By: _____

Vendor Authorized Signature

Printed Name & Title

Vendor Company Name



J.M. Perry
Chief Procurement Officer

Issued: 9-9-2010

BID PROPOSAL

BID SCHEDULE – REVISED PER ADDENDUM #4

HERNANDO COUNTY UTILITIES DEPARTMENT

WEEKI WACHEE WASTEWATER TREATMENT PLANT BYPASS PROJECT

Item	Description	Unit	Quantity	Unit Price	Total
1	Mobilization and Demobilization	LS	1		
2	Bonding and Insurance	LS	1		
3	Surveying (As Built)	LS	1		
4	Maintenance of Traffic	LS	1		
	<u>FURNISH AND INSTALL FORCE MAIN AND GRAVITY MAIN</u>				
5	2" PVC Force Main-Open Cut	LF	110		
6	4" PVC C-900 DR18 Force Main-Open Cut	LF	2000		
7	4" Fusible PVC C-900 DR18 Force Main-HDD	LF	180		
8	6" PVC C-900 DR18 Force Main-Open Cut	LF	2650		
9	6" Fusible PVC C-900 DR18 Force Main-HDD	LF	300		
10	8" PVC C-900 DR18 Force Main-Open Cut	LF	4590		
11	8" Fusible PVC C-900 DR18 Force Main-HDD	LF	150		
12	8" PVC DR26 Gravity Main-Open Cut	LF	400		
13	8" PVC DR26 Gravity Main-Open Cut Through Limestone	LF	1000		
14	10" PVC C-900 DR18 Force Main-Open Cut	LF	15800		
15	10" Fusible PVC C-900 R18 Force Main-HDD	LF	2550		
16	10" HDPE DR11 Force Main-HDD	LF	220		
	<u>FURNISH AND INSTALL WATER MAIN</u>				
17	1" PVC-Open Cut	LF	45		
18	6" PVC C-900 DR18-Open Cut	LF	2550		
	<u>FURNISH AND INSTALL MANHOLES</u>				
19	Fiberglass Manholes (48-inch dia, 9-12 ft deep)	EA	4		
	<u>LIFT STATION</u>				

BID PROPOSAL

BID SCHEDULE – REVISED PER ADDENDUM #4

HERNANDO COUNTY UTILITIES DEPARTMENT

WEEKI WACHEE WASTEWATER TREATMENT PLANT BYPASS PROJECT

Item	Description	Unit	Quantity	Unit Price	Total
20	<u>Cofer Road Master Lift Station</u>				
	Fiberglass Wetwell (8 ft dia x 20 ft deep)	EA	1		
	(2) EBARA Model 100 DLMFU622 450 GPM @ 130 ft TDH -30 HP or equal(w/rails, control panel, electrical and mechanical accessories)	LS	1		
	Concrete Valve Vault	LS	1		
	Elevated Platform	LS	1		
	Data Flow Tower	LS	1		
	Odor Control Unit (Zabac Model 42)	EA	1		
	DI Piping and Valve	LS	1		
21	<u>Bayport Lift Station Upgrade</u>				
	(2) EBARA Model 100 DLMU622 Pumps 450 GPM @ 130 TDH-30 HP (w/ control panel, rails, electrical and mechanical accessories)	LS	1		
22	Portable Emergency Generator	LS	1		
	<u>FURNISH AND INSTALL VALVES</u>				
23	2" Combination Air Release Valve Assembly, 4" Force Main	EA	1		
24	2" Combination Air Release Valve Assembly, 6" Force Main	EA	2		
25	2" Combination Air Release Valve Assembly, 8" Force Main	EA	3		
26	2" Combination Air Release Valve Assembly, 10" Force Main	EA	12		
27	2" Gate Valve	EA	1		
28	4" Gate Valve	EA	3		
29	6" Check Valve	EA	1		
30	6" Gate Valve	EA	7		
31	8" Gate Valve	EA	4		

BID PROPOSAL

BID SCHEDULE – REVISED PER ADDENDUM #4

HERNANDO COUNTY UTILITIES DEPARTMENT

WEEKI WACHEE WASTEWATER TREATMENT PLANT BYPASS PROJECT

Item	Description	Unit	Quantity	Unit Price	Total
32	10" Gate Valve	EA	6		
	<u>FURNISH AND INSTALL FITTINGS</u>				
33	2" 45 Deg. MJ Fittings	EA	4		
34	4" 11.25 Deg. MJ Fittings	EA	2		
35	4" 45 Deg. MJ Fittings	EA	8		
36	6" 11.25 Deg MJ Fittings	EA	4		
37	6" 45 Deg MJ Fittings	EA	8		
38	6"x6" MJ Wye	EA	1		
39	8" 11.25 Deg. MJ Fittings	EA	4		
40	8" 45 Deg. MJ Fittings	EA	10		
41	10" x 4" MJ Wye	EA	1		
42	10" x 2" MJ Tee	EA	1		
43	10"x 8" MJ Reducer	EA	1		
44	10"x6" MJ Wye	EA	1		
45	10" x6" MJ Reducer	EA	1		
46	10" 11.25 Deg. MJ Fittings	EA	12		
47	10" 22.5 Deg. MJ Fittings	EA	8		
48	10" 45 Deg. MJ Fittings	EA	24		
49	6"x6" Full Circle Stainless Steel Tapping Sleeve & Valve	EA	1		
50	2" MJ Cap	EA	2		
51	4" MJ Cap	EA	2		
52	6" MJ Cap	EA	10		
53	10" MJ Cap	EA	1		
	<u>CONNECTIONS</u>				
54	New 8" Gravity Main w/Ex. Manhole @ LS01	LS	1		
55	New 8" Gravity Main w/Ex. Cofer Road Wetwell	LS	1		
56	New 10" Force Main w/Ex. Manhole at US19	LS	1		
57	New 6" Force Main w/ Ex. 6" Force Main at Cortez Blvd.	LS	1		

BID PROPOSAL

BID SCHEDULE – REVISED PER ADDENDUM #4

HERNANDO COUNTY UTILITIES DEPARTMENT

WEEKI WACHEE WASTEWATER TREATMENT PLANT BYPASS PROJECT

Item	Description	Unit	Quantity	Unit Price	Total
58	New 4" Force Main w/ Ex. 4" Force Main at Westside Avenue	LS	1		
59	New 6" Water Main w/Ex. 10" Water Main at Shoal & Cofer	LS	1		
60	Wet Tap New 6" Water Main at Cofer Road	LS	1		
	<u>MISCELLANEOUS</u>				
61	Demolition (Wastewater Treatment Plant and LS 01)	LS	1		
62	Audio-Video Pre/Post Construction Inspection	LS	1		
63	Asphalt Driveway/Roadway Restoration	SY	200		
64	Concrete Sidewalk Restoration	SY	100		
65	Remove Asbestos Cement Pipe	LF	10		
66	Hydraulic Grouting	CY	100		
67	Select Fill # 57 Stone	CY	350		
68	Select Fill Sand	CY	350		
69	6" PVC Removal	LF	3500		
70	Sod	LS	1		
71	Erosion Control	LS	1		
	Total				
	<u>BID ALTERNATIVE</u>				
72	Furnish and Install 6" HDPE DR 11 Force Main-HDD	LF	180		
73	Furnish and Install 8" HDPE DR 11 Force Main-HDD	LF	300		
74	Furnish and Install 10" HDPE DR 11 Force Main-HDD	LF	150		
75	Furnish and Install 12" HDPE DR 11 Force Main-HDD	LF	2550		
				Grand Total	