

ADDENDUM NO. 3

TO
THE CONTRACT DOCUMENTS
FOR THE HERNANDO COUNTY UTILITIES DEPARTMENT
THE US19/SR50 FORCE MAIN PROJECT
IN

HERNANDO COUNTY, FLORIDA

SOLICITATION NO. 10-0085

REVISED BID DATE: Wednesday, September 22, 2010 at 3:00 p.m.

NOTICE

BIDDERS ARE REQUIRED TO ACKNOWLEDGE RECEIPT OF
THIS ADDENDUM BY SIGNATURE AT THE BOTTOM OF
THIS ADDENDUM IN THE SPACES PROVIDED AND
RETURNED AT THE TIME OF THE BID DATE.

To All Bidders:

This Addendum forms a part of the Contract Documents and modifies the Bidding Documents dated August 2010 with amendments and additions noted below. Acknowledge receipt of this Addendum in the space provided in the Bid Form. Failure to do so may disqualify the Bidder.

Changes to the Project Bid Specifications

1. Bid Item No. 19 has been revised from 275 LF to 100 LF. Refer to revised Bid Schedule.
2. Bid Item No. 27 has been deleted and leave blank in revised Bid Schedule.
3. On sheets 6 & 7 of plans a 10" gravity sewer main should be shown coming from the south into the collector manhole located just east of the existing US 19 lift station. Also, the gravity main from the collector manhole to the existing US 19 lift station is a 15" instead of an 8". In addition, a camlock connection exists on the pig port located on the existing 8" force main shown on sheet 7. Contractor can either connect at camlock for bypass pumping or connect to existing force main at another location of his choosing.

ACKNOWLEDGMENT

By: _____

Vendor Authorized Signature

Printed Name & Title

Vendor Company Name



J.M. Perry
Chief Procurement Officer

Issued: 9/16/2010

BID PROPOSAL

BID SCHEDULE – REVISED PER ADDENDUM #3

HERNANDO COUNTY UTILITIES DEPARTMENT

US 19/SR 50 PUMP STATION AND FORCE MAIN REPLACEMENT PROJECT

Item	Description	Unit	Quantity	Unit Price	Extended Price
1	Mobilization and Demobilization	LS	1		
2	Bonding and Insurance	LS	1		
3	Surveying (As Built)	LS	1		
4	Maintenance of Traffic	LS	1		
5	US 19/SR 50 LIFT STATION RECONSTRUCTION	LS	1		
6	Wastewater Pumping System	LS	1	\$366,825	\$366,825
7	Housing/Air Conditioned Pre-Fabricated Building for VFD Control Panel	LS	1		
8	Odor Control System	LS	1		
9	New Emergency Generator	LS	1		
10	Surge Protection System	LS	1	\$124,196.58	\$124,196.58
	<u>PIPING</u>				
11	Furnish & Install 10" PVC Force Main C-900 DR 18	LF	40		
12	Furnish & Install 12" PVC Force Main C-900 DR 18	LF	20		
13	Furnish & Install 16" PVC Force Main C-905 DR 18	LF	50		
14	Furnish & Install 18" PVC Force Main C-905 DR 18	LF	15,200		
15	Furnish & Install 20" PVC Force Main C-905 DR 18	LF	10,800		
16	Furnish & Install 24" PVC Force Main C-905 DR 18	LF	80		
17	Furnish and Install 18" Fusible PVC C-905 DR 18	LF	4,600		
18	Furnish and Install 18" PVC C-905 Jack and Bore- 36" Casing	LF	150		
19	Furnish and Install 20" PVC C-905 Jack and Bore-42" Casing	LF	100		
	<u>VALVES</u>				
20	Furnish & Install 2" Air Release/Vacuum Combination Valve Assembly for 18" Force Main	EA	12		

21	Furnish & Install 2" Air Release/Vacuum Combination Valve Assembly for 20" Force Main	EA	5		
22	Furnish & Install 10" Gate Valve	EA	1		
23	Furnish & Install 12" Gate Valve	EA	1		
24	Furnish & Install 16" Gate Valve	EA	1		
25	Furnish & Install 18" Gate Valve	EA	12		
26	Furnish & Install 20" Gate Valve	EA	8		
	<u>FITTINGS AND PIPE JOINT RESTRAINT</u>				
27	-----	-----	-----	-----	-----
28	Furnish and Install 16" 45 Deg. MJ Fittings	EA	2		
29	Furnish and Install 18" 45 Deg. MJ Fittings	EA	34		
30	Furnish and Install 20" 11.25 Deg. MJ Fittings	EA	5		
31	Furnish and Install 20" 22.5 Deg. MJ Fittings	EA	2		
32	Furnish and Install 20" 45 Deg. MJ Fittings	EA	16		
33	Furnish and Install 20" MJ Tee	EA	1		
34	Furnish and Install 20"x10" MJ Reducer	EA	1		
35	Furnish and Install 20"x18" MJ Reducer	EA	13		
36	Furnish and Install 20"x10" MJ Tee	EA	1		
37	Furnish and Install 24"x20" MJ Reducer	EA	1		
38	Furnish and Install 24"x24"x16" MJ Wye	EA	1		
	<u>CONNECTIONS</u>				
39	Tooke Lake Lift Station	LS	1		
40	Glen Wastewater Treatment Plant Force Main	LS	1		
41	Weeki Wachee High School	LS	1		
	<u>MISCELLANEOUS</u>				
42	Color Audio Video Records	LS	1		
43	Concrete Mitered End Section and associated drainage piping	EA	32		
44	Sod	LS	1		
45	Erosion Control	LS	1		
46	Removal 6" RWM	LF	1500		
	Total				
	<u>BID ALTERNATIVE</u>				
17A	Furnish & Install 20" HDPE Force Main DR-11- HDD	LF	4,600		